


IN-DASH STEREO INSTALLATION KIT FOR 2007-10 MAZDA CX-9



INTRODUCTION/PRELIMINARY

This premium installation kit is for 2007-10 Mazda CX-9 vehicles. Included are all the parts you need to mount your car stereo or CD player into your vehicle's dash. Refer to the individual instruction in this manual to remove your vehicle's factory radio and assemble the kit.

CAUTION

DISCONNECT YOUR VEHICLE'S NEGATIVE BATTERY TERMINAL BEFORE THE INSTALLATION TO HELP PREVENT ELECTRICAL DAMAGE. WE RECOMMEND THE USE OF A VOLT/OHM METER OVER A TEST LIGHT TO CHECK WIRING. A TEST LIGHT OR GROUNDED WIRE PROBE CAN CAUSE DAMAGE TO THE VEHICLE'S COMPUTER AND/OR DIAGNOSTIC SYSTEMS. AVOID ALL FACTORY AIRBAG WIRING - AIRBAGS CAN ACCIDENTALLY DEPLOY CAUSING SERIOUS INJURY OR DEATH.

NOTES

- See your vehicle's instructions for any special tools your installation might require.
- Read all instructions accompanying your car stereo for proper wiring and mounting instructions.

FACTORY WIRING CODES

For Factory Wiring Codes go to: www.scosche-cars.com

CAR STEREO CONNECTORS

PROVIDE EASY CONNECTION OF YOUR CAR STEREO TO FACTORY WIRING HARNESS.

MAO3B

2000-Up Mazda
Power/speaker

HAAB

2005-up Honda
Antenna Adapter



LIABILITY DISCLAIMER

This instruction booklet is based on carefully documented data and research of automobile dash disassembly, wire harness/codes and information pertaining to installation of this kit (MA1545B) in 2007-10 Mazda CX-9 vehicles. Scosche Industries, Inc. cannot be held responsible for discrepancies/inconsistencies that may occur due to the automobile manufacturing changes or options, or damage that may occur in the automobile during the installation of components while using this booklet.

If you have any further questions, call our toll free technical help line at: **1-800-621-3695x3**

FACTORY STEREO REMOVAL


2007-10 MAZDA CX-9

1. With panel removal tool, unclip and remove panels located on the left & right side of the radio and A/C controls.
2. Unclip shifter panel, unplug and remove.
3. Extract (1) Phillips head screw securing pocket in front of shifter then with panel removal tool, unclip pocket, unplug and remove.
4. Extract (2) Phillips head screws securing the top portion of the radio/AC panel then with panel removal tool, unclip, unplug and remove panel.
5. Extract (4) Phillips head screws and (1) 10mm screw securing radio, unplug and remove.

MOUNTING THE STEREO

SINGLE DIN MOUNT

1. Attach 6552 pocket to 7079 panel using screws supplied with kit (see left).
2. Attach 6593 and 6594 mounting brackets to 7079 panel using supplied screws (see below).
3. Align and attach aftermarket single din stereo to brackets using the hardware supplied with the aftermarket stereo. **Note:** If hardware is not supplied with aftermarket stereo use hardware from factory stereo
4. Reconnect stereo and finish assembly.



DOUBLE DIN MOUNT

1. Attach 6593 and 6594 mounting brackets to 7079 panel using supplied screws.
2. Align and attach aftermarket double din stereo to brackets using the hardware supplied with the aftermarket stereo. **Note:** If hardware is not supplied with aftermarket stereo use hardware from factory stereo.
4. Reconnect stereo and finish assembly.

